HAPAM DOUBLE BREAK DISCONNECTOR RETROFIT





Client : Northern Power Grid

Location: Saltholme, UK

BEFORE RETROFIT (HAPAM MAKE)







2 Sets (2 x 3= 6 Poles) of 145kV Double break need to be replaced

AFTER RETROFIT (S&S MAKE)





ISSUES IDENTIFIED AT SITE

* Aging of Disconnector change of Complete isolator including drive box due to Operation difficulty

CHALLENGES FACED

- * Disconnector fixing Without change in existing structure, High level Mounting
- * Fitment of Isolator within stipulated time period within the Warehouse space
- * Matching the Drive box position with Torque bearing fixing provision

SOLUTION PROVIDED

- * New enhanced Live parts replacement
- * Installation as per customer requirement to match the Existing switch mounting position

